BRUHAT BANGALORE MAHANAGARA PALIKE, YELAHANKA ZONE

Executive Engineeer
Byatarayanapura Division
B.B.M.P., Bangalore - 92

DRAFT TENDER SCHEDULE

Issued to :

Original / Duplicate
Item No. 8

Name of Work: Providing metalling and Asphalting to C Krishnappa layout and Kempanna layout in Ward No. 10.

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
1	156.42	KSRRB 300-1. Earth work excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications complete as per specifications MORTH ~~chapter 3. No. 149/ Item No. 19.1/ PWD SR 2011-12.~~ and Directions of Engineer-IN-charge	Cu m	62.86	
2	3910.50	Scarifying existing stone metal layer upto 75mm thick along with their bituminous surface, picking up scarified materials and stacking of old serviceable materials with lead of 100 m. sequential spreading of the salvaged aggregates with fresh aggregates on prepared base and consolidating as per water bound macadam specifications including cost of all labour, HOM of machineries complete as per specifications ~~.Page No. 171/ Item No. 21.3/ PWD SR 2011-12~~ and Directions of Engineer-IN-charge	Sqm	68.36	
3	547.47	KSRRB M400-17: Providing, laying spreading and compacting graded stones aggregate to wet mix macadam specifications including premixing the material with water at OMC in mechanical mix plant carriage of mixed method of tipper to site, laying, in uniform layers with paver in sub base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per MORTH specification ~~NO. 406, Page No. 166/ Item No. 20.18/ PWD SR 2011-12~~ and Directions of Engineer-IN-charge.	Cu m	1060.56	
4	3910.50	KSRB 500-1. Cleaning the existing WBM road surface including removing of binding materials and other foreign matter with wire brushes and small picks, sweeping with brooms or soft brushes and finally dusting with old gunny bags and / or compressed air, to recieve bituminous treatment including cost of all materials, labour, HOM of machineries complete as per specifications ~~.Page No. 171/ Item No. 21.1/ PWD SR 2011-12~~ and Directions of Engineer - IN-charge.	Sqm	10.04	

5	3910.50	KSRRB 500-9: providing and applying tack coat on granular base such as WBM and WMM surfaces hot bitumen primed at 4 kg per 10 sqm, heating bitumen in boiler fitted with spray set (excluding cleaning of road surface)including cost of all materials, labour, HOM of machineries complete as per specifications. ~~page No. 172/ Item No. 21.9/ PWD SR 2011-12~~ and Directions of Engineer-in-charge	Sqm	26.63	
6	97.76	KSRRB M500-18: Providing and laying **semi dense bituminous concrete 25mm thick with 100-120 TPH** batch type HMP producing an average output of 75 tonnes per hour using crushed aggregates of specified grading, premixed with bituminous binder at 4.5 to 5% of mix and filler, transporting the hot mix to work site, laying with a hydrostatic paver finisher with sensor control to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem roller to achieve the desired compaction as per MORTH specifications clause No. 500.8 complete in all respects as per specifications. -do- 25-30mm compacted thickmess with 5% bitumen 80/100 using 40-60 HMP usinf mechanical paver (Grading-II) ~~No. 174/ Item No. 21.20.5 / PWD SR 2011-12~~ as per Specification and directions of Engineer-in-charge.	Cu m	9045.45	
7	156.42	Lead for Disposal of Debris shall be payable at carriage rates by Mechanical means inlcuding loading and unloading. From 0.00 to 5.00 Km (Page No.123)	Cu m	to be 81.00 Deleted	

Signture of the Contractor

Executive Engineer
Byatarayanapura Division
BBMP, Bangalore - 92

ಕರಡು ಟೆಂಡರ್ ಷಡ್ಯೂಲ್‌ನ್ನು
ತಿದ್ದುಪಡಿಗಳ ಸಂಖ್ಯೆ Seven (7)
ತಿದ್ದುಪಡಿ ಮಾಡಿ/ಇಲ್ಲದೆ
ಅನುಮೋದನೆ ನೀಡಲಾಗಿದೆ.

ಅಧೀಕ್ಷಕ ಅಭಿಯಂತರರು
ಯಲಹಂಕ ವಲಯ
ಬಿಬಿಎಂಪಿ, ಬೆಂಗಳೂರು-92